

Rig #17 – 350 or 450 HP Workover Rig

Available 2-3 weeks from deposit.

Rig was built to be 450 HP. Construction was halted to allow buyer to choose Paint Color, Horsepower and options.

450 HP Information is under Option heading below.

RIG SPECS
- All Brand NEW carrier (18" I - beam) Frame
- 4 axle carrier
- 44,000 pounds each rear axle
- 12,000 pound each front axle
- All Brand NEW wheels & tires front & Brand NEW tires on back
- '86 model 8 V71 Detroit (318 HP) Engine
- '86 model 626 Allison Transmission
- '82 Cooper 1028 Draw-works w/ high & low
- 250 gal. Splash water cooling system on Draw-works
- '96 ft. 200,000 lbs + Wilson type Derrick (NEWLY Constructed)
- 100 Ton Wilson Blocks (3 sheaves)
- All brand NEW hydraulic system (50 GPM Flow)
- Brand NEW hydraulic tank (170gal.)
- Brand NEW hydraulic leveling jacks on front & back
- Brand NEW work floor
- NEW paint job (your choice of colors)
RIG DIMENSIONS
- Length center front axle & center rear axle (24' 5")
- Carrier total length (38' 3")
- Carrier total width (8' 8")
- Approximately total overall height (13' 10")
- Approximately overall length (56' 5")
OPTIONAL ITEMS
- 11,000 ft 9/16" swab line and new drill line
- Tubing Power tongs - (Rod Power tongs included)
- 60 series Detroit Engine (475 HP) & a 4460 Allison Transmission
- Floating 5th axle - needed to increase to 450HP depth capabilities

