

Description	Rig #2
UPPER DOG HOUSE 10' x 30' V-CRIMP WALLS WITH LOCKERS, SATELLITE DRILLER, WEIGHT INDICATOR MARTIN DECKER TYPE D, AND 4 PIN DRILLING RECORDER. <b>(NEW)</b>	1
NATIONAL 80B 1600 HP DRAWWORKS WITH 3 ENGINE COMPOUND (REBUILT) AND MASTER SKIDDED WITH 2 QUINCY 325 AIR COMPRESSORS, NEW EATON DISC BRAKE, CROWN-O-MATIC, AND 2-8000# HYDRAULIC WINCHES IN PLACE OF CAT HEADS.	1 @ 1600 HP
MUD SYSTEM WITH AGITATORS WITH MUD FLOW TROUGHS, INTERNAL AND EXTERNAL PLUMBING WITH 5" x 6" CENTRIFUGAL PUMPS WITH PLUMBING, V-CRIMPED WALLS <b>(ALL NEW)</b>	3 TANK @ 1,250BBL
V-CRIMP MUD HOUSE WITH STAND <b>(NEW)</b>	1 @ 8' x 30'
CANTILEVER TYPE MAST WITH 5 SHEAVE CROWN AND CROWN STAND, ALL SANDBLASTED, PAINTED.	24' x 136' 769,000#
CATWALK WITH 3 SETS OF PIPE RACKS <b>(NEW)</b>	60" WIDE x 80' LONG x 18" TALL
DOUBLE HYDRAULIC BLOWOUT PREVENTOR AT 10000# WORKING PRESSURE WITH 10000# TOP AND STUDDED 10000# BOTTOM <b>(NEW)</b>	1 @ 13 5/8"
CHOKE MANIFOLD <b>(NEW)</b>	1 @ 4"
AIR HOIST (REBUILT OR NEW)	1 @ 5000#
IRON ROUGHNECK (REBUILT)	1
ELECTRICAL INSTALLATION AND COMPLETE REWIRE OF ENTIRE RIG <b>(NEW)</b>	1
DRILLING LINE W/ STAND <b>(NEW)</b>	3000' x 1 1/4"
KELLY HOSE <b>(NEW)</b>	3" x 55'
UPPER AND LOWER KELLY VALVE	1
ENTIRE RIG AND ALL COMPONENTS SANDBLASTED AND PAINTED	1
DOUBLE LINEAR MOTION SHAKER <b>(NEW)</b>	1
10" – 2 CONE DESANDER <b>(NEW)</b>	1
5" – 10 CONE DESILTER <b>(NEW)</b>	1
F-1000 1000 HP TRIPLEX MUD PUMPS <b>(NEW)</b>	2

Description	Rig #2
CAT 398 ENGINES TO DRIVE MUD PUMPS (REBUILT WITH ZERO HOURS)	2
CENTRIFUGAL 75HP CHARGER PUMPS FOR MUD PUMPS ( <b>NEW</b> )	2 @ 5" x 6"
VIBRATING HOSES ( <b>NEW</b> )	2 @ 3.5"
VOLVO 1642-VE ENGINES 650 HP WITH NEW TWIN DISC TORQUES TO DRIVE DRAWWORKS ( <b>NEW WITH 2 YEAR UNLIMITED HOUR WARRANTY</b> )	3
KOOMEY ACCUMULATOR UNIT WITH PLUMBING ( <b>NEW</b> )	8 Station
GENERATOR HOUSE WITH 2 VOLVO ENGINES WITH 540KW GENERATOR SETS, GE CONTROLS, QUINCY 390 COMPRESSOR, AND RECEPTACLE OUTLETS ( <b>ALL NEW WITH 2 YEAR UNLIMITED HOUR WARRANTY</b> )	10' x 50'
NATIONAL ROTARY TABLE WITH BUSHING (REBUILT)	27.5" x 53.25"
BLOCK/HOOK (REBUILT)	1 @ 350 ton
SWIVEL (REBUILT)	1 @ 400 ton
V-CRIMP FUEL TANK WITH BUILT IN 4 COMPARTMENT LUBESTER WITH TWO ELECTRIC FUEL PUMPS ( <b>NEW</b> )	12,000 Gallon
WIRELINE UNIT ( <b>NEW</b> )	20,000'
<ul style="list-style-type: none"> <li>• <i>Additional Accident Protection Features</i></li> <li>• <i>Warranties on Motors and Engines</i></li> <li>• <i>Well Cycle Times are Improved</i></li> <li>• <i>Depth Flexibility</i></li> <li>• <i>Highly Mobile</i></li> </ul>	

**Disclaimer:**

The Company offers the details of this equipment in good faith but cannot guarantee or warrant the accuracy of this information nor warrant the condition of the equipment. A buyer should instruct his agents, or his surveyors, to investigate such details as the buyer desires validated. This equipment is offered subject to prior Price, price change, or withdrawal without notice

**Pictures of Rig #2**

