

<b>Drawworks</b>
Oilwell E-2000, 2000 HP, grooved for 1-3/8" drill line with two (2) refurbished G.E. 752 series wound DC traction motors, Baylor 7838 Auxiliary Brake, make-up and break-out catheads
<b>Mud Pumps</b>
Two (2) WeatherFord MP-16, 1600 HP packages each with master skid, two (2) refurbished G.E. 752 series wound DC traction motors, drive sheaves, belts, belt guards, charge pump, liner wash system, etc.
<b>Mast</b>
DSI 142', 1,000,000#SHL with crown containing six (6) main cluster sheaves and one (1) fastline sheave. Mast to include racking board, raising lines, etc.
<b>Substructure</b>
DSI 30' High Box-On-Box, 1,000,000# casing, 600,000# setback, complete with two (2) sets of stairs from drill floor to ground, one (1) set of stairs from drill floor to water tank. v-door, mousehole and rathole.
<b>Rig Power</b>
NOV (Ross-Hill) 4x4 SCR System/Control House with 1000 KVA main transformer, 225 KVA lighting transformer and adequate MCC to operate the rig. Three (3) Caterpillar 3512C diesel engines each with Caterpillar SR4, 1750 KVA generator and radiator.
Each generator set to be packaged on a 10' wide x 40' long master skid with roof, muffler, etc.
Two (2) 30 HP compressors, cold start, air dryer and two (2) volume tanks to be included
<b>Mud System</b>
1500 BBL., 3-tank mud system complete with eight (8) 10 HP agitators, four (4) 8x6 centrifugal pumps with 75 HP motors, 2- Linear Shakers. 2-Cone Desander, 16 Cone Desilter, Vacuum Degasser and mix hopper.
<b>Miscellaneous</b>
<ul style="list-style-type: none"> <li>○ Driller's Side Dog house</li> <li>○ Parts/Change House</li> <li>○ 500 Ton block, hook and swivel</li> <li>○ 37.5" Rotary Table</li> <li>○ Deadline And-ror</li> <li>○ Brake Cooling Tank with two (2) 4x3 pumps with 30 HP motors and heat exchanger.</li> <li>○ Choke Manifold and Mud/Gas Separator</li> <li>○ 6-Station Closing Unit</li> <li>○ 13-5/8', 10,000# Single and Double BOP</li> <li>○ 13-5/8", 5,000# Annular</li> <li>○ Fuel Tank with transfer pumps</li> <li>○ Water Tank/Trip Tank with pumps</li> <li>○ Five Star Surveyor Wireline Unit</li> <li>○ Drill Line Spooler with 7500' of 1-3/8" Dril Line</li> <li>○ Rig to be completely rigged up and tested in Houston. Texas.</li> </ul>