

Description	Rig #3
UPPER DOG HOUSE 10' x 30' V-CRIMP WALLS WITH LOCKERS, SATELLITE DRILLER, WEIGHT INDICATOR MARTIN DECKER TYPE D, AND 4 PIN DRILLING RECORDER. <b>(NEW)</b>	1
SKYTOP BREWSTER N-75 1000 HP DRAWWORKS WITH 2 ENGINE COMPOUND AND MASTER SKIDDED WITH 2 QUINCY 325 AIR COMPRESSORS, NEW EATON DISC BRAKE, CROWN-O-MATIC, AND 2-8000# HYDRAULIC WINCHES IN PLACE OF CAT HEADS.	1 @ 1,000 HP
MUD SYSTEM WITH AGITATORS WITH MUD FLOW TROUGHS, INTERNAL AND EXTERNAL PLUMBING WITH 5" x 6" CENTRIFUGAL PUMPS W/PLUMBING, V-CRIMPED WALLS <b>(ALL NEW)</b>	2 TANK @ 1,000 BBL
V-CRIMP MUD HOUSE WITH STAND <b>(NEW)</b>	8' x 30'
CATWALK WITH 3 SETS OF PIPE RACKS <b>(NEW)</b>	60" WIDE x 80' LONG x 18" TALL
11" HYDRIL ANNULAR BLOWOUT PREVENTOR AT 5000# WORKING PRESSURE WITH STUDDED TOP AND FLANGED BOTTOM <b>(NEW)</b>	1
CHOKE MANIFOLD <b>(NEW)</b>	1 @ 4"
AIR HOIST (REBUILT OR NEW)	1 @ 5000#
IRON ROUGHNECK (REBUILT)	1
ELECTRICAL INSTALLATION AND COMPLETE REWIRE OF ENTIRE RIG <b>(NEW)</b>	1
DRILLING LINE W/ STAND <b>(NEW)</b>	3000' x 1 1/4"
KELLY HOSE <b>(NEW)</b>	1 @ 3" x 55'
UPPER AND LOWER KELLY VALVE	1
ENTIRE RIG AND ALL COMPONENTS SANDBLASTED AND PAINTED	1
DOUBLE LINEAR MOTION SHAKER <b>(NEW)</b>	1
10" – 2 CONE DESANDER <b>(NEW)</b>	1
5" – 10 CONE DESILTER <b>(NEW)</b>	1
SWIVEL (REBUILT)	1 @ 250 ton
BLOCK/HOOK (REBUILT)	1 @ 250 ton

Description	Rig #3
GENERATOR HOUSE WITH 2 VOLVO ENGINES WITH <u>325KW</u> GENERATOR SETS, GE CONTROLS, QUINCY 390 COMPRESSOR, AND RECEPTACLE OUTLETS <b>(ALL NEW WITH 2 YEAR UNLIMITED HOUR WARRANTY)</b>	10' x 35'
WIRELINE UNIT <b>(NEW)</b>	15,000'
BOX ON BOX SUBSTRUCTURE WITH BUILT IN AIR TANK	18' H
CANTILEVER TYPE MAST WITH 5 SHEAVE CROWN AND CROWN STAND, ALL SANDBLASTED, PAINTED.	18.6' x 131' 500,000#
VOLVO TAD-1630 ENGINES 550 HP WITH NEW TWIN DISC FLUID COUPLINGS TO DRIVE DRAWWORKS <b>(NEW WITH 2 YEAR UNLIMITED HOUR WARRANTY)</b>	2
MZ-9 1000 HP TRIPLEX MUD PUMPS <b>(NEW)</b>	2
CAT 398 ENGINES TO DRIVE MUD PUMPS (REBUILT WITH ZERO HOURS)	2
CENTRIFUGAL 75HP CHARGER PUMPS FOR MUD PUMPS <b>(NEW)</b>	2 @ 5" x 6"
VIBRATING HOSES <b>(NEW)</b>	2 @ 3.5"
NATIONAL ROTARY TABLE WITH BUSHING (REBUILT)	20.5" x 53.25"
KOOMEY ACCUMULATOR UNIT WITH PLUMBING <b>(NEW)</b>	5 Station
V-CRIMP FUEL TANK WITH BUILT IN 4 COMPARTMENT LUBESTER WITH TWO ELECTRIC FUEL PUMPS <b>(NEW)</b>	8,000 Gallon
<ul style="list-style-type: none"> <li>• <i>Additional Accident Protection Features</i></li> <li>• <i>Warranties on Motors and Engines</i></li> <li>• <i>Well Cycle Times are Improved</i></li> <li>• <i>Depth Flexibility</i></li> <li>• <i>Highly Mobile</i></li> </ul>	

**Disclaimer:**

The Company offers the details of this equipment in good faith but cannot guarantee or warrant the accuracy of this information nor warrant the condition of the equipment. A buyer should instruct his agents, or his surveyors, to investigate such details as the buyer desires validated. This equipment is offered subject to prior Price, price change, or withdrawal without notice

Pictures of Rig #3

