

| SUBSTRUCTURE | |
|--|---|
| SUBSTRUCTURE & HEIGHT | GRASSHOPPER STYLE-SELF RISING 19' CLEAR HT. |
| ROTARY CAPACITY | 500,000 LBS |
| SET – BACK CAPACITY | 240,000 LBS |
| | |
| MAST | |
| MAST HEIGHT | 145 FT. |
| STATIC HOOK LOAD | 450,000 LBS |
| CASING STABBING BASKET | ELECTRIC |
| FINGER BOARD (RACKING CAPACITY) WITH ELECTRIC OR AIR MULE TUGGER @ RACKING BOARD | 13,200 FT |
| LINE'S (CROWN BLOCK) GROOVED FOR WHAT SIZE LINE | 5-SHEAVE/FAST 1 & 1/4" |
| | |
| (2) BOOM POLES (OPTIONAL) | 2-HYDRO. |
| | |
| DRAWWORKS | |
| HP ELECTRIC OR MECHANICAL | 1K-SCR |
| DYNAMIC BRAKE | 30KW-EDDY |
| CROWN – O – MATIC | SCEC |
| DRILL LINE SIZE & TYPE | 1 & 1/4 AMCO |
| | |
| TOP DRIVE | |
| TON CAPACITY API & TYPE | 250-TON/DQ40-BC |
| TUBING SIZES | 1 & 1/2" |
| RPM (ROTATION) | ADJ-500 HP 29,200 FT-LBS |
| | |
| TRAVELING BLOCK/HOOK | |
| TON CAPACITY | 225 TON |
| | |
| ROTARY TABLE | |
| SIZE | 27.5" ELECTRIC |
| RPM & STATIC WGT CAPACITY | VARY-500K |
| BUSHINGS FOR RUNNING OF CASING | 17-1/2 TO 4.5" |
| | |
| ELEVATOR LINKS | |
| TON | 400 TON & SHORTIES |
| | |
| IRON ROUGHNECK | |
| TYPE | VARCO |
| | |

| WENCHES | |
|---|--|
| (2) 5-TON WENCHES ON RIG FLR | YES |
| (1) 1-TON ELECTRIC OR AIR WENCH IN DERRICK TO HANDLE DRILL COLLARS | YES |
| | |
| MUD PUMPS & HIGH PRESSURE SYSTEM | |
| PUMPS | 2 @ 1300 HP |
| 2" – 5,000 LBS CONNECTION FLANGE RELIEF VALVES | 5,000 LB. |
| SUCTION FILTER, DISCHARGE FILTER AND IN-LINE FILTER | YES |
| CHARGING PUMPS | 2 EACH |
| 5" LINES FROM PUMPS 5,000 PSI | YES |
| MANIFOLD & STANDPIPE | YES – 5" NOMINAL WITH 5,000# (DOUBLE) |
| 2" X 5,000 PSI WP – 5" X 5,000# ON WELDED VALVES WITH HAMMER UNIONS | YES |
| 5" X 2" REDUCER | YES |
| TYPE (D) PRESSURE GAGE | YES |
| STAND PIPE (5") WITH GOOSE NECK GRADE 160 WITH HAMMER UNIONS | YES |
| (2) KELLY HOSES | 5,000# WITH 5,000# GASKET |
| | |
| LOW PRESSURE MUD SYSTEM | |
| HOPPERS | 2 EACH |
| ELECTRIC AC MOTORS 6" X 8" | YES - (FOR MIXING MUD IN PRE-MIX TANK) |
| (1) 1,200 RPM ELECTRIC AGITATOR | YES/VARY (IN EACH COMPARTMENT) |
| BARREL'S OF ACTIVE MUD SYSTEMS | 1147 BBL. |
| BARREL'S OF RESERVE MUD | 95 BBL. |
| BARREL'S OF FRESH WATER | 400 BBL. |
| 80 BARREL TRIP TANK | 65 BBL |
| GAS BUSTER | POORBOY 100 |
| | |
| GENERATORS & POWER | |
| (1) SCR CONTROL BUILDING TO MEET CAPACITY | YES |
| GENERATOR SETS & KW EACH | 2EA/1530 |
| 600V/480 VOLT/220 | ALL IN SCR-CONTROL |
| | |
| WELL CONTROL SYSTEMS | |
| DIVERTER SYSTEM | HYDR-ELEC. 5K |

| | |
|---|------------------------------|
| BOP ANNULAR FOR SPUDDING IN | 11" |
| BOP ANNULAR DRILLING | 11" |
| DOUBLE & SINGLE RAM TYPE | 4.5" |
| DRILLING SPOOLS | 5K |
| HCR VALVE 5" | 5000 PSI |
| KILL LINE – 3 ½" SCH. 180 WITH VALVE – 10,000 PSI MANUAL + HYDRAULIC / RETURN VALVE | ALL |
| CHOKE LINE & HYDRAULIC VALVE | 3"&5" |
| 3,000 PSI ACCUMULATOR CONTROL UNIT WITH 1 ELECTRIC AND 2 AIR PUMPS | YES |
| 10,000 PSI CHOKE MANIFOLD H2S RESISTANT | N/A |
| 10,000 KELLY COCK HOSE | 5000 PSI |
| FLOW VALVE | CUSTOM |
| SLIPS & ELEVATORS | |
| TOOLPUSHER'S HOUSE | 12X36' |
| COMPANY/OPERATOR'S HOUSE | 12X36' |
| MECHANIC/ELECTRICIAN'S SHOP | 12X36' |
| DRILLER'S HOUSE ON RIG FLR | DRILLERS MODULE ON RIG FLOOR |
| CREW CHANGE HOUSE | 12X36' |
| DRILL STEM | |
| DRILL PIPE | 5.5" (HARDBAND & COATED) |
| HEAVY WATER | 5.5" |
| DRILL COLLARS | 6-8"/24-6" |
| CAMPS | |
| SLEEPER'S CAMPS | 2-CREW/2-MODULES |
| MESS ROOM / GALLERY | IN CREW QUARTERS |
| LAUNDRY ROOMS | IN UTILITY MODULE |

Disclaimer:

The Company offers the details of this equipment in good faith but cannot guarantee or warrant the accuracy of this information nor warrant the condition of the equipment. A buyer should instruct his agents, or his surveyors, to investigate such details as the buyer desires validated. This equipment is offered subject to prior Price, price change, or withdrawal without notice

