

Description	Rig #9 - Diesel
25' H x 54' LONG BOX ON BOX SUBSTRUCTURE WITH 1,500,000# RATING W/ BUILT IN CHANGE ROOM, BUILT IN PARTS ROOM, (2) 800 GALLON AIR VOLUME TANKS, V- DOOR, SAFETY RAILS, 4 SETS OF STAIRS, GRASSHOPPER, COMPETE NEW WIRING AND PLUMBING, 1,500,000# HERCULES DEADLINE ANCHOR - (NEW)	1
UPPER DOG HOUSE 10' X 30' V-CRIMP WALLS WITH LOCKERS, SATELLITE DRILLER, WEIGHT INDICATOR MARTIN DECKER TYPE D, AND 4 PIN DRILLING RECORDER. (NEW)	1
UPPER DOG HOUSE 10' X 30' V-CRIMP WALLS WITH PARTS ROOM AND REMOTE CHOKE ROOM (NEW)	1
30' x 152' PYRAMID CANTILEVER TYPE MAST 1,000,000# WITH 5" x 10,000# STAND PIPE, 6 SHEAVE WITH 1 FAST LINE CROWN AND CROWN STAND, ALL SANDBLASTED, PAINTED (REBUILT)	1
60" X 18" X 60' CATWALK WITH 3 SETS OF 18" X 30' PIPE RACKS (NEW)	1
ELECTRICAL INSTALLATION AND COMPLETE REWIRE OF ENTIRE RIG (NEW)	1
ENTIRE RIG AND ALL COMPONENTS SANDBLASTED AND PAINTED	1
SCR 5-STATION 1600AMP SIEMENS SCR CONTROL HOUSE (NEW)	1
3512C CATERPILLAR, 1476 HP, 1200 RPM ENGINES WITH CAT MODEL SR4B 1750KVA, 1225KW, 2 BEARING GENERATOR 600VAC 3PHASE 60HZ, WITH 56 SQ FT HIGH AMBIENT RADIATORS, BUILT IN OIL PANS UNDER ENGINES FOR OIL RECOVERY, 2007 MODELS (NEW)	4
INGERSOLL RAND ROTARY SCREW SSR-EP60-125, AIR COOLED, 460 VOLT, 400 GALLON RECEIVER TANK, WITH NEMA 1 WITH OPEN DRIP PROOF MOTOR AND FULL VOLTAGE STARTER (NEW)	2
ELECTRICAL AND PLUMBING SUITCASES (NEW)	5
NATIONAL/IDEAL 125 2000 HP DRAWWORKS DIESEL ELECTRIC, WTM AIR BRAKE, POWERED BY (2) GE 752 TRACTION MOTORS WITH BLOWERS, CROWN-O-MATIC, AND 2-8000# HYDRAULIC WINCHES IN PLACE OF CAT HEADS (REBUILT AND NEW)	1
500 TON NATIONAL BLOCK/HOOK (REBUILT)	1

Description	Rig #9 - Diesel
500 TON NATIONAL SWIVEL (REBUILT)	1
500 TON TESCO OR VARCO TOP DRIVE (NEW OR REBUILT)	1
27.5" X 53.25" NATIONAL ROTARY TABLE WITH BUSHING (REBUILT) WITH BUSHING AND (1) GE 752 TRACTION MOTOR WITH BLOWER (REBUILT)	1
5.25" X 46' HEX KELLY W/ DRIVE BUSHING AND ROTARY HOSE (NEW)	1
3.5" X 65' GATES KELLY HOSE (NEW)	1
3.5" GATES VIBRATING HOSES (NEW)	3
5000' X 1 3/8" UNION DRILLING LINE WITH DRILLING SPOOL STAND (NEW)	1
JT/FOUR INTERNATIONAL IRON ROUGHNECK MODEL IR-2100-R (REBUILT)	1
HYDRAULIC POWER UNIT FOR IRON ROUGHNECK (REBUILT)	1
HYDRAULIC POWER UNIT FOR FLOOR WINCHES (NEW)	1
TANK 2000BBL MUD SYSTEM WITH 15HP AGITATORS, WITH MUD FLOW TROUGHS, INTERNAL AND EXTERNAL PLUMBING WITH 5" X 6" CENTRIFUGAL 75HP PUMPS W/ PLUMBING, V-CRIMPED WALLS (ALL NEW)	4
1300 HP TRIPLEX MUD PUMPS (NEW) WITH (4) DC G/E TRACTION MOTORS AND BLOWERS (REBUILT)	2
50BBL TRIP TANK AND 3" X 4" CENTRIFUGAL PUMP (NEW)	1
8' X 30' V-CRIMP MUD HOUSE WITH (2) MIXING HOPPERS, ELECTRIC PANEL AND TRANSFORMER INSTALLATION AND STANDS (NEW)	1
5" X 6" CENTRIFUGAL 75 HP CHARGER PUMPS FOR MUD PUMPS (NEW)	3
10" 3-CONE MCM O'DRILL DESANDER (NEW)	1
5" 16-CONE MCM O'DRILL DESILTER (NEW)	1
MCM O'DRILL LINEAR MOTION SHAKERS (NEW)	2

Description	Rig #9 - Diesel
INGERSOLL RAND 5000# AIR HOIST (NEW)	2
INGERSOLL RAND 1500# AIR HOIST ON CATWALK (NEW)	1
13 5/8" ANNULAR BLOWOUT PREVENTOR 5000# WORKING PRESSURE WITH STUDDERED TOP AND 10000# FLANGED BOTTOM (NEW)	1
13 5/8" SINGLE HYDRAULIC BOP AT 10000# WORKING PRESSURE WITH 10000# TOP AND STUDDERED 10000# BOTTOM (NEW)	1
13 5/8" X 10000# X 4 1/16" MUD CROSS WITH (2) OUTLETS (NEW)	1
SETS 5" PIPE RAMS (NEW)	2
SET OF BLIND RAMS (NEW)	1
4 1/16" X 10000# CHOKE MANIFOLD (NEW)	1
20000' WIRELINE UNIT (NEW)	1
UPPER AND LOWER KELLY VALVE (NEW)	1
6 STATION USA OIL TOOLS ACCUMULATOR UNIT WITH PLUMBING (NEW)	1
12000 GALLON V-CRIMP FUEL TANK WITH BUILT-IN 4 COMPARTMENT LUBESTER (NEW)	2
500BBL V-CRIMP WATER TANK W/ 2- 2" X 3" CENTRIFUGAL 20 HP WATER PUMPS (NEW)	1

Disclaimer:

The Company offers the details of this equipment in good faith but cannot guarantee or warrant the accuracy of this information nor warrant the condition of the equipment. A buyer should instruct his agents, or his surveyors, to investigate such details as the buyer desires validated. This equipment is offered subject to prior Price, price change, or withdrawal without notice

Pictures of Rig #9

