

Description	Rig #9
25' H x 54' LONG BOX ON BOX SUBSTRUCTURE WITH 1.5M RATING W/ BUILT IN CHANGE ROOM, BUILT IN PARTS ROOM, AIR TANK, V-DOOR, SAFETY RAILS, 4 SETS OF STAIRS, COMPETE NEW WIRING AND PLUMBING, DEADLINE ANCHOR (NEW)	1
UPPER DOG HOUSE 10' X 30' V-CRIMP WALLS WITH LOCKERS, SATELLITE DRILLER, WEIGHT INDICATOR MARTIN DECKER TYPE D, AND 4 PIN DRILLING RECORDER. (NEW)	1
21.6' x 142' CANTILEVER TYPE MAST 1000000# WITH 5 SHEAVE CROWN AND CROWN STAND, ALL SANDBLASTED, PAINTED	1
NATIONAL 125 2000 HP DRAWWORKS WITH 2 ENGINE COMPOUND AND MASTER SKIDDED WITH 2 QUINCY 325 AIR COMPRESSORS, NEW EATON DISC BRAKE, CROWN-O-MATIC, AND 2-8000# HYDRAULIC WINCHES IN PLACE OF CAT HEADS.	1
CAT 399 ENGINES OR CAT 3512 ENGINES WITH NATIONAL C-300 TORQUE CONVERTORS FOR DRAWWORKS (DYNOTESTED WITH PAPERS)	2
4 TANK 1600BBL MUD SYSTEM WITH AGITATORS, WITH MUD FLOW TROUGHS, INTERNAL AND EXTERNAL PLUMBING WITH 5" X 6" CENTRIFUGAL PUMPS W/ PLUMBING, V-CRIMPED WALLS (ALL NEW)	1
F1300 HP TRIPLEX MUD PUMPS (NEW)	2
8' X 30' V-CRIMP MUD HOUSE WITH STAND (NEW)	1
CAT 399 ENGINES OR CAT 3512 ENGINES TO DRIVE MUD PUMPS (DYNO TESTED WITH PAPERS)	2
5" X 6" CENTRIFUGAL 75 HP CHARGER PUMPS FOR MUD PUMPS (NEW)	2
GENERATOR HOUSE 10' X 50' WITH TWO VOLVO ENGINES WITH 560KW GENERATOR SETS, V-CRIMP WALLS, GE CONTROLS, QUINCY 390 COMPRESSOR, AND RECEPTACLE OUTLETS (ALL NEW WITH 2 YEAR UNLIMITED HOUR WARRANTY)	1
400 TON NATIONAL P-400 SWIVEL ((REBUILT))	1
350 TON SOWA BLOCK/HOOK (NEW)	1

Description	Rig #9
6 STATION KOOMEY ACCUMULATOR UNIT WITH PLUMBING ((REBUILT) OR NEW)	1
60" X 60' CATWALK WITH 3 SETS OF PIPE RACKS (NEW)	1
13 5/8" ANNULAR BLOWOUT PREVENTOR 5000# WORKING PRESSURE WITH STUDDED TOP AND FLANGED BOTTOM (NEW)	1
3 5/8" SINGLE HYDRAULIC BOP AT 10000# WORKING PRESSURE WITH 10000# TOP AND STUDDED 10000# BOTTOM (NEW)	1
3 5/8" DOUBLE HYDRAULIC BOP AT 10000# WORKING PRESSURE WITH 10000# TOP AND STUDDED 10000# BOTTOM (NEW)	1
4" CHOKE MANIFOLD ((REBUILT) OR NEW)	1
20000' WIRELINE UNIT (NEW)	1
27.5" X 53.25" NATIONAL ROTARY TABLE WITH BUSHING ((REBUILT))	1
5.25" X 46' HEX KELLY W/ DRIVE BUSHING AND ROTARY HOSE	1
5000# AIR HOIST ((REBUILT) OR NEW)	1
IRON ROUGHNECK ((REBUILT))	1
12000 GALLON V-CRIMP FUEL TANK WITH BUILT IN 4 COMPARTMENT LUBESTER (NEW)	1
500BBL V-CRIMP WATER TANK W/ 2- 2" X 3" CENTRIFUGAL 20 HP WATER PUMPS (NEW)	1
ELECTRICAL INSTALLATION AND COMPLETE REWIRE OF ENTIRE RIG (NEW)	1
3000' X 1 3/8" DRILLING LINE W/ STAND (NEW)	1
3.5" X 55' KELLY HOSE (NEW)	1
3.5" VIBRATING HOSES (NEW)	2
UPPER AND LOWER KELLY VALVE	1
ENTIRE RIG AND ALL COMPONENTS SANDBLASTED AND PAINTED	1

Description	Rig #9
DUAL LINEAR MOTION SHAKER (NEW)	1
10" 2 CONE DESANDER (NEW)	1

Disclaimer:

The Company offers the details of this equipment in good faith but cannot guarantee or warrant the accuracy of this information nor warrant the condition of the equipment. A buyer should instruct his agents, or his surveyors, to investigate such details as the buyer desires validated. This equipment is offered subject to prior Price, price change, or withdrawal without notice

WWW.BUYRIGS.COM

Pictures of Rig #9

